

Completion
of
M/V KAPITAN GREGORIO OCA

Keel laying April 10th, 2018
Launching August 9th, 2018
Delivery December 25th, 2018

Principal Particulars

Length over all 78.60m
Length bet.P.P 70.00m
Breadth molded 12.00m
Depth molded 5.55m / 8.05m
Draft molded 4.99m
Gross Tonnage 2,098tons
Sea speed 13.8knots (Output : 85%MCR, Sea margin : 0%)
Complement 138P (Crew : 24P, Trainer : 6P, Cadet : 108P)
Main engine DAIHATSU DIESEL MFG. CO., LTD.
..... 6DKM-26eL (1,471kW) 1set
Auxiliary engine DAIHATSU DIESEL MFG. CO., LTD.
..... 6DE-18 (530kW) 2sets
Radio equipment FURUNO ELECTRIC CO., LTD.
Design Bulbous bow, Double continuous deck

